

Project Purpose & Description



Project Purpose

The purpose of the Highway 4 project is to achieve a smooth ride, replace poor utilities beneath the highway, and to enhance pedestrian accommodations.

Project Description


Highway 4 through the City of St. James is in poor condition and in disrepair. The city utility infrastructure is also in poor condition and is currently experiencing multiple breaks each winter. MnDOT received municipal consent for the proposed project in December 2014. The project includes reconstruction of approximately 1.6 miles of Highway 4, including two new mini-roundabouts.

Project elements include:

- Reconstruct Highway 4 from approximately 200 feet south of 10th Avenue S. to 11th Ave N.
- Realign 7th Avenue S. to address the skew and increase safety
- Construct mini-roundabouts at the two existing signals on 1st Ave S.
- Provide back-in angle parking on 1st Ave S.
- Replace existing sidewalks and install new sidewalks
- Bring all pedestrian accommodations up to American's with Disability Act (ADA) standards
- Improve boulevard aesthetics and safety
- Upgrade storm sewer throughout the corridor
- Update lighting standards and fixtures

Project Schedule:

Apr. – Sept. 2015.....Project design
 Oct. 2015 – Jan. 2016Agency approvals
 Feb. – Apr. 2016.....Project bidding
 May – Nov. 2016.....Planned construction



Highway 4 at 1st Avenue South



Mini Roundabouts

The two mini-roundabouts will be constructed at the intersection of 1st Ave S. with Armstrong Blvd and 1st Ave S. with 7th St S. Mini-roundabouts are much smaller than traditional roundabouts, allowing for its construction within a physically constrained location. They are an ideal intersection for two-lane urban intersections. They provide better safety, traffic flow, fuel efficiency and air quality.

The mini-roundabouts will contain approach lanes with a median to ensure drivers are slowing down prior to entering the intersection. The center of the mini-roundabouts will contain a central island, which

is surrounded by a continuous travel lane. The mini-roundabout is designed to allow passenger cars to use the travel lanes as they travel around the central island. Buses and trucks may travel over the central island to complete turning movements.

Quick Facts:



- 1/2 the overall motorist delay of a traffic signal
- 1/3 fewer vehicles stopping than with a traffic signal
- 1/3 less vehicle emissions and fuel consumption
- 1/4 decrease in crashes anticipated
- Shorter pedestrian crossings

Back-In Angle Parking



Back-in angle parking will be constructed on the south side of 1st Ave S. between 7th Street S and Armstrong Blvd. Back-in angle parking provides a reduced risk of crashes, improves visibility, simplifies parking maneuvers, and improves loading and unloading of vehicles.

Quick Facts:

- Parking maneuver is similar to but easier than parallel parking
- Vehicle doors and trunk are more readily accessible from sidewalk
- Improved visibility of traffic when leaving the stall



Construction Staging Layout



BLUE PHASE
 Hwy 4 Between 5th Ave N & 8th Ave N
 7th Ave N Between 8th St N & 7th Ave N
Design Considerations:
 -Full Roadway/Sidewalk Reconstruction
Timeline:
 Flexible


BLUE PHASE
 8th Ave N Between 6th St N & Swanson Ave
Design Considerations:
 -Sanitary Sewer System Low Point
 -Utility Replacement/ Associated
 Roadway Improvements
Timeline:
 Flexible

RED PHASE
 Hwy 4 - Between 2nd Ave S & 5th Ave N
Design Considerations:
 -Traffic Signal Removal
 -Two Mini-Roundabouts
 -Back-In Angle Parking
 -Full Roadway/Sidewalk Reconstruction
Timeline:
 Early Season Completion For Local
 Business Traffic

GREEN PHASE
 Hwy 4 Between 7th Ave S & 2nd Ave S
Design Considerations:
 -7th St S Roadway Closure
 -Full Roadway/Sidewalk Reconstruction
Timeline:
 Flexible

GREEN PHASE
 Hwy 4 Between 11th St S & 7th Ave S
Design Considerations:
 -7th St S Roadway Re-alignment
 -Full Roadway/Sidewalk Reconstruction
Timeline:
 Flexible


Partial Traffic Mobility
 Maintained Throughout
 Construction



DRAFT
 SUBJECT TO CHANGE

RED PHASE
 Hwy 4 Between 10th Ave S & 7th Ave S
Design Considerations:
 -Sidewalk Construction East of Hwy 4
 -Full Roadway Reconstruction
Timeline:
 Completed Before Or After The
 Watonwan County Fair

St. James HIGHWAY 4 Reconstruction



C.R. 57 (10TH AVE. S.)